



Condensation Roofing Update

Dear Patrons,

Thank you all for your feedback and concerns regarding the issue with the condensation at the Coburg Basketball Stadium.

Sports Stadiums Victoria have engaged the services of Roofrite to conduct the following:

REPLACE THE FIBREGLASS SHEETING

- Remove existing fibreglass roof sheets.
- Supply and install 26x 13m 0.48 zinculume Trimclad iron roof sheets, to be laid over 50mm Anticon insulation blanket.

EQUIPMENT HIRE – CRANE

- Crane hire required to meet Worksafe OH&S safe work requirements for safe lifting of materials onto ROOF

EQUIPMENT HIRE - GUARDRAIL

Supply and install guardrail to meet Worksafe OH&S safe work access requirements.

RUBBISH REMOVAL

Correctly dispose of the old fibreglass sheets.

Sports Stadiums Victoria has paid a deposit for the works to be completed and is currently in talks with Roofrite as to how to logistically coordinate these works with as little disruption as possible to stadium operations.

A confirmed date will hopefully be finalised next week with works most likely commencing early September.

Up until installation date the condensation policy implemented some two weeks ago will be utilised if required.

Thank you for your patience regarding this matter and with these works being completed over the next month or so we should not have any issues with the condensation moving forward.

Regards
Rod Leonard
Sports Stadiums Victoria
Operations Manager